# Weeping Tile Disconnection to Reduce the Impact of Basement Flooding London, Ontario



September 19, 2013

**City of London** 

Environmental and Engineering Services Department



#### Today's presentation

- Document a pilot project involving weeping tile disconnection, initiated by the City of London
- Objective to decrease Inflow and Infiltration in the sanitary sewers to reduce the risk of basement flooding
- Project undertaken Summer 2013




#### Outline

- Terminology
- Background:
  - What causes basement flooding?
- Pilot Project: Sherwood Forest Subdivision





# Terminology





### Sump Pump Diagram







#### Basement Flooding

- What is Inflow/Infiltration (I/I)?
  - Stormwater and/or groundwater entering sanitary sewers
- Excessive I/I can lead to surcharged/overloaded sanitary main
  - Widespread issue, generally affects multiple homes on a street



#### Sources of I/I

- Weeping tile connections
  - Lot grading sloped towards house
  - Downspout discharge location (at or near foundation wall).
  - Clay soils
- Combined sewers
- Old pipes, cracks, etc



# London's Weeping Tile History

- Prior to 1985:
  - weeping tile connected to sanitary sewer
- 1985-1995:
  - weeping tile connected to sump pit; sump pump discharge to surface
- 1995-present:
  - weeping tile connected to sump pit; sump pump discharge to storm sewer PDC



#### **Sherwood Forest Subdivision**

- Subdivision developed late 1970s to early 1980s
- Historical basement flooding prone area








#### Flow Monitors


Blanchard Crescent, May 2009





#### Flow Monitors

Ardsley Crescent, May 2009






### What's Happening?

- Weeping tile connected to sanitary → most homes pre 1985
- Clay soils → do not absorb water
- Lot grading has settled over the years →
  - water falling from the sky is draining towards houses
- Zero lot line homes →
  - Closely spaced together = high % of roof and hard surface
- Poorly placed downspout discharge locations



#### **Aerial Photos**







## Downspouts











# Private Side Alternative: Advantages

- Disconnecting the weeping tile from sanitary:
  - Removes I/I at the source
  - Saves pumping and treatment costs
  - Reduces risk of overwhelming system with 'next big storm'
  - Significantly more cost effective:
    - → only 20% of the cost of public side alternative



#### **Existing Grant Program**

- Voluntary (Current Practice):
  - 75% Grant Program for Basement Flooding Protection (includes sump pump, backwater valve, weeping tile disconnection, storm PDC)
  - Very low uptake; 'dry basement' homeowners have no interest, even though they are contributing.



### Proposed Pilot Project

- Pilot Disconnection on Blanchard (up to 65 homes)
- City pays 100% cost + provides additional \$1,000 for future maintenance;
  - Includes disconnection of weeping tile, installation of sump pump, backwater valve, and private storm sewer lateral (PDC)



#### Proposed Pilot Project

- Voluntary signup; 50% of homeowners participation required
  - Computer modeling determined that we needed 50% buy in to ensure that enough stormwater was removed from the sanitary system (to prevent basement flooding)
- Individual site visits to each home to determine retrofit feasibility



#### Getting Buy In

- Homeowner Buy In
  - Public meeting to inform and educate homeowners; introduce them to our proposed solution
  - Initially had 27 homes signed up for full disconnection
  - Ended up with 32 home disconnections + 5 storm PDC installs



### Tendering Project

#### 1. External works tender

installation of storm PDCs from sewer main to house;
 included restoration, road resurfacing

#### 2. Internal works tender

- Very unique tender from City prospective
- Included all items necessary for disconnection of weeping tile from sanitary, installation of sump pump, installation of backwater valve
- Tender items for electrical, laminate flooring removal and replacement, drywall, etc.



#### **Project Cost**

#### **External Works**

Tender bid \$305,000 (\$8,245 per house)

#### **Internal Works:**


•Tender bid: \$172,000 (\$5,375 per house)

Total = \$477,000

#### Note:

- external works include asphalt resurfacing
- only one Internal bid received; interested capable plumbing contractors were not familiar with City contract bonding requirements







#### Project Logistics

 Major difference from all other City led projects: we were proposing to undertake work on private property AND <u>inside</u> private homes!

#### Legal concerns:

- contractor required to have police records checks for all workers
- Additional liability insurance
- Comprehensive Dishonesty, Disappearance and Destruction Coverage (\$20,000 per employee)



#### **Project Coordination**

#### City's Building Division:

- Required to obtain building permits for each house (contractor's responsibility)
- Contractor needs to acknowledge that inspections can impact their schedule



#### **Project Coordination**


#### **Homeowners:**

- Consent to enter agreements from each homeowner
- Site visits before, during, and after project
- •Contractor needed a flexible schedule to accommodate homeowner work schedule, appointments, etc.



#### **External Works**

- Protect lawns
- Many PDCs installed using directional drilling method
- Minimized impact to lawns, gardens, etc





### External Works – Tight work spaces


Working in between fences





# External works – landscaping considerations


- Storm PDC with cleanout
- Working beside nice rose bushes, other landscaping features important to homeowner





#### **External Works**

 Adjacent to gas meters, plants/shrubs





#### **Internal Works**


Tight work spaces





# Retrofit - Sump Pumps







#### Retrofit – Sump Pump and Backwater Valve






# Retrofit – sump pump and backwater valve







#### Retrofit - Hardwood floors





#### Backwater valves







#### Homeowner Challenges

- Anticipated Challenges
  - Scheduling
  - Duration of work in house
  - Clean up
  - Late sign ups people wanting to sign up only after construction began
  - Exempt fully finished basements; logistically too difficult to retrofit and restore



#### **Optics**


- Some Concerns from Homeowners;
  - Why aren't you replacing the sidewalk/curb/driveway apron/road?
  - Some had the expectation that since "The City" was coming to do work, that the entire streetscape would be replaced to brand new
  - Reality: we were using sewer \$ to fix a basement flooding issue; did not have the \$ to focus on curb/sidewalk, etc.
  - What impact will the sump pump have on my home?
  - Are you installing a backup system?



#### **Post Construction**


- To date, pilot project is a success; homeowners generally pleased with work
- Real test will be significant rain event
- Flow monitor in sanitary sewer directly downstream of project
- Ongoing monitoring will take place









# Post construction – Preliminary flow monitoring


















#### Preliminary Results

- No wet weather impacts appear for Blanchard Crescent in comparison to Ardsley Crescent, which had a large wet weather response
- Initial monitoring suggests the Blanchard disconnection program is a success



#### Next Steps

- Present the project findings to homeowners
- Initiate another street of disconnections given our success
- Investigate geotechnical conditions to determine if more targeted weeping tile disconnections can be done; are soil conditions and groundwater levels only in certain pockets of a given street?



#### Thank You

**Kyle Chambers, P.Eng. City of London** 

Environmental and Engineering Services Department

kjchambe@london.ca

519.661.2500 x5854

